



**NOTES:**

1. REBAR SHALL BE CONTINUOUS THROUGH THE JOINT (NO SPLICES).
2. CONCRETE SHALL BE MIN. SIX SACK MIX. (3250 P.S.I. MIN. IN 28 DAYS).
3. WOOD FORMS SHALL HAVE A NOMINAL THICKNESS OF 2", EXCEPT ON CURVE CONST. WHERE THE THICKNESS SHALL BE DETERMINED BY THE CITY INSPECTOR. FORMS SHALL REMAIN FOR A MIN. OF 24 HOURS.
4. HEADERS SHALL BE USED AT THE EDGE OF PAVEMENT EXCEPT WHEN BUILDINGS OR OTHER PERMANENT IMPROVEMENTS ABUT THE ALLEY, AND SHALL BE LEFT IN PLACE AFTER CONST. THEY SHALL BE FOUNDATION GRADE OR BETTER.
5. INSTALL EXPANSION JOINTS EVERY 48' IN VALLEY GUTTER.

<b>CITY of CORCORAN • Department of Public Works</b>		
Standard Drawing for:		05/19/08 Date
<b>ALLEY DETAILS</b>	APPROVED: City Engineer	
Revised:		<b>C-7</b>